

Innovations in Full Depth Reconstruction of Interstate Roadways in Arizona

Tad Niemyjski, P.E.
ADOT Geotechnical Services Section

Arizona Pavement/Materials Conference
November 16, 2023

Winter of 2022/2023



Winter of 2022/2023

- Abnormally wet winter with many days of snow accumulation
- 14,327 labor hours used 20 snow plows on I-40 between Ash Fork and Joseph City to clear road

Winter of 2022/2023

- This weather took a toll on older highway pavements
- Older sections of I-40 and I-17 experienced significant failures with major pothole development

Introduction

Two reconstruction projects to be discussed

- Southbound I-17, County Line to McConnell
- I-40, Cataract Lake to Parks
- Several challenges to project estimation and construction were encountered

I-17 Southbound

- Rehabilitation of 29 miles south from Flagstaff to the Coconino County Line
- Existing roadway is primarily PCCP pavement with friction course overlay
- New pavement would be PCCP with 1.5 inch leveling course of AC



I-17 Pavement in 2020

Became much
worse during last
winter



Taking a peak at
the PCCP slabs
in 2020

Pieces of
concrete pulled
out with a rock
pick



Pavement Core in
failed pavement
area



Full depth cracking of PCCP slabs was observed in many locations.

Southbound I-17

- Scoping Challenge: amount of PCCP that would have to be replaced during construction
- Standard pavement coring and crack mapping was conducted
- GPR Survey of about 54 lane-miles of highway was completed in April of 2020


Mobile GPR Survey



Photo provided by
Infrasense

Innovations in subsurface investigation

Excessive water content within the base course materials was suspected to be an issue contributing the the roadway failures.





Many areas of
I-17 displayed
water
accumulation

GPR Indicating Voids and Moisture





Image provided by
Infrasense

Innovations in subsurface investigation

Pavement deterioration mapping of both lanes was developed based on GPR data.



Concrete deterioration mapping




Image provided by
 Infrasense

I-17 Southbound

- Construction began in the mid-2022 and continued this past construction season.
- Full depth reconstruction areas used CTB beneath the replaced PCCP pavement.
- Project costs are anticipated to exceed the construction estimate by about 5%.

I-17 Southbound nearly completed this fall



I-40, Cataract Lake to Parks

- Section of I-40 was constructed in about 1967
- Scoped as a pavement rehabilitation project
- 17 miles of full depth pavement reconstruction
- Began at Williams and extended to Parks, Arizona

Full depth failures east of Williams, 2017



I-40, Cataract Lake to Parks

- Several areas of pavement showed signs of full depth failure during the winter of 2016/2017
- Project used cement to stabilize the existing cinter base materials
- Project was completed in 2018



Cement was blended into the existing cinder base to improve base stability and strength.

Cataract Lake to Parks today

- Five winters have passed since construction began.
- The pavement within the limits of this project currently shows no signs of distress.

I-40 today, east of Williams today



I-40 today, near Parks



Lessons Learned, I-17

- Not everything goes according to plan.
- GPR evaluation of pavement condition seemed to be reasonably accurate however some extra work for the contractor was identified.
- I-17 SB project originally budgeted \$45 Mil. for construction, anticipated overrun of about 5%.

Lessons Learned, Cataract Lake

- I-40 Cataract Lake project has performed well.
- The roadway surface currently shows insignificant signs of wear or distress.
- Cement treatment of base materials has proven to be a cost effective method for base improvement.

Questions?

